

ARKANSAS DEPARTMENT OF TRANSPORTATION

050475

LITTLE PINEY CREEK STR. & APPRS. (S)

FEDERAL AID PROJECT NHPP-0033(29)

THE PURPOSE OF THIS PROJECT IS TO REPLACE ONE STRUCTURE ON HIGHWAY 56 IN IZARD COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, CONCRETE DITCH PAVING, MINOR DRAINAGE, EROSION CONTROL, RUMBLE STRIPS, PAVEMENT MARKING, CONSTRUCT ONE TRIPLE R.C. BOX CULVERT (38.75'), AND MISC. ITEMS.

ROUTES: 56

SECTIONS: 2

COUNTY: IZARD

LENGTH: 0.123 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	7.00	STA
201111	GRUBBING	7.00	STA
202011	R&D OF FENCE	833.00	LF
202096	R&D OF PIPE CULVERTS	2.00	EACH
205011	REMV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210213	UNCLASSIFIED EXCAVATION	7,238.00	CUYD
210611	COMPACTED EMBANKMENT	3,699.00	CUYD
210702	SOIL STABILIZATION	100.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	2,531.00	TON
401011	TACK COAT	619.00	GAL
406161	M.A. IN ACHM BINDER(1")	108.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	5.00	TON
407162	MA IN ACHM SURFACE(1/2")	1,374.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	86.00	TON
412002	COLD MILLING ASPHALT PVMT.	489.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	4.00	TON
415011	ACHM PATCH.EXIST.RDWY.	4.00	TON
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
603024	24" TEMPORARY CULVERT	80.00	LF
603072	72" TEMPORARY CULVERT	240.00	LF
604003	SIGNS	298.00	SQFT
604013	BARRICADES	32.00	LF
604023	TRAFFIC DRUMS	36.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	193.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	193.00	LF
604041	CONST.PAVEMENT MARKINGS	9,660.00	LF
604083	VERTICAL PANELS	36.00	EACH
605012	CONC.DITCH PAVING(TYPE B)	889.00	SQYD
605606	24" R.C.PIPE CULVERTS(CL.3)	4.00	LF
605858	24" FES R.C.PIPE CLVT.	12.00	EACH
606703	18" SIDE DRAIN	32.00	LF
606704	24" SIDE DRAIN	80.00	LF
606705	30" SIDE DRAIN	40.00	LF

606994	SELECTED PIPE BEDDING	20.00	CUYD
611008	4" PIPE UNDERDRAINS	500.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	2.00	EACH
619028	WIRE FENCE (TYPE D)	720.00	LF
620001	LIME	3.00	TON
620011	SEEDING	1.71	ACRE
620022	MULCH COVER	9.90	ACRE
620030	WATER	349.10	MGAL
621001	TEMPORARY SEEDING	8.19	ACRE
621021	SILT FENCE	431.00	LF
621031	SAND BAG DITCH CHECKS	495.00	BAG
621071	SEDIMENT BASIN	180.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	180.00	CUYD
621111	SEDIMENT REMOVAL & DISPOSAL	237.00	CUYD
621151	ROCK DITCH CHECKS	60.00	CUYD
623001	SECOND SEEDING APPLICATION	1.71	ACRE
624001	SOLID SODDING	604.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	1.00	EACH
637011	MAILBOX SUPPORTS (SINGLE)	1.00	EACH
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	907.00	LF
718002	REFL.PAINT PVMT.MRK.WH(6")	1,700.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	1,700.00	LF
721002	RAISED PAVEMENT MARKERS-2	42.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	1.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	2.00	EACH
731075	TEMP. IMPACT ATTENUATION BARRIER (RELO)	1.00	EACH
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	149.00	CUYD
802012	CLASS S CONCRETE-ROADWAY	314.41	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	38,380.00	LB
816003	FILTER BLANKET	353.00	SQYD
816111	DUMPED RIPRAP	176.00	CUYD

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHING FOUR HUNDRED FIFTY (450) CALENDAR DAYS.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 10.0%.