

ARKANSAS DEPARTMENT OF TRANSPORTATION

070591

HWY. 7 CABLE MEDIAN BARRIER IMPVTS. (S)

FEDERAL AID PROJECT HSIP-5270(2)

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT APPROXIMATELY 13.54 MILES OF CABLE MEDIAN BARRIER ON HIGHWAY 7 IN OUACHITA AND UNION COUNTIES. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, CONCRETE DITCH PAVING, GUARDRAIL, WIRE ROPE SAFETY FENCE, EROSION CONTROL, AND MISC. ITEMS.

ROUTES: 7

SECTIONS: 2 & 3

COUNTY: OUACHITA & UNION

LENGTH: 13.54 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202052	R&D OF APPROACH GUTTERS	22.00	EACH
202132	R&D OF GUARDRAIL	4,925.00	LF
210213	UNCLASSIFIED EXCAVATION	368.00	CUYD
210611	COMPACTED EMBANKMENT	820.00	CUYD
303117	AGGR.BASE COURSE(CLASS 7)	2,874.00	TON
407162	MA IN ACHM SURFACE(1/2")	487.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	31.00	TON
504264	APPROACH GUTTERS	214.14	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,473.00	SQFT
604023	TRAFFIC DRUMS	494.00	EACH
604071	ADVANCE WARNING ARROW PANEL	130.00	DAY
604078	PORT.CHANGEABLE MESSAGE SIGN	56.00	WEEK
605012	CONC.DITCH PAVING(TYPE B)	56,946.00	SQYD
617005	GUARDRAIL (TYPE A)	5,500.00	LF
617105	TERMINAL ANCHOR POSTS (TYPE 1)	4.00	EACH
617312	GUARDRAIL TERMINAL (TYPE 2)	19.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	31.00	EACH
618351	WIRE ROPE SAFETY FENCE	66,468.00	LF
618353	WIRE ROPE SAFETY FENCE MAINT. MATERIALS	1.00	L.S.
618354	WIRE ROPE SAFETY FENCE (POST REPAIR)	50.00	EACH
620001	LIME	10.00	TON
620011	SEEDING	5.22	ACRE
620022	MULCH COVER	18.35	ACRE
620030	WATER	986.20	MGAL
621001	TEMPORARY SEEDING	13.13	ACRE
621031	SAND BAG DITCH CHECKS	1,320.00	BAG
621051	DROP INLET SILT FENCE	1,500.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	91.00	CUYD
621169	FILTER SOCK (18")	17,705.00	LF
623001	SECOND SEEDING APPLICATION	5.22	ACRE
624001	SOLID SODDING	14,773.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
734011	BRIDGE END TERMINAL	1.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	20,982.00	LB

THIS PROPOSAL CONTAINS THE JOB SPECIAL PROVISION "SITE USE (A+C METHOD)-CALENDAR DAY CONTRACT" FOR BIDDING IN WHICH THE BIDDER WILL DETERMINE THE NUMBER OF CALENDAR DAYS TO COMPLETE THE PROJECT.

THE PERCENTAGE GOAL FOR DISADVANTAGED BUSINESS ENTERPRISE (DBE) PARTICIPATION IN THIS PROJECT IS 12.0%.