

DATE REVISED	DATE REVISED	FED. RD. DIST. NO.	STATE	JOB NO.	SHEET NO.	TOTAL SHEETS
07/19/2024		6	ARK.	101126	18	43
SUMMARY OF QUANTITIES AND REVISIONS						



DIGITALLY SIGNED 07-19-2024

### SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	QUANTITY	UNIT
201	CLEARING	3	STATION
201	GRUBBING	3	STATION
202	REMOVAL AND DISPOSAL OF FOUNDATIONS	1166	SQ. YD.
202	REMOVAL AND DISPOSAL OF PIPE CULVERTS	13	EACH
202	REMOVAL AND DISPOSAL OF GUARDRAIL	362	LIN. FT.
SP, SS, & 210	UNCLASSIFIED EXCAVATION	8594	CU. YD.
SP & 210	COMPACTED EMBANKMENT	11639	CU. YD.
SP & 210	SOIL STABILIZATION	200	TON
SP, SS, & 303	AGGREGATE BASE COURSE (CLASS 7)	6751	TON
SS & 401	TACK COAT	722	GAL.
SP, SS, & 406	MINERAL AGGREGATE IN ACHM BINDER COURSE (1")	621	TON
SP, SS, & 406	ASPHALT BINDER (PG 70-22) IN ACHM BINDER COURSE (1")	26	TON
SP, SS, & 407	MINERAL AGGREGATE IN ACHM SURFACE COURSE (1/2")	1831	TON
SP, SS, & 407	ASPHALT BINDER (PG 64-22) IN ACHM SURFACE COURSE (1/2")	15	TON
SP, SS, & 407	ASPHALT BINDER (PG 70-22) IN ACHM SURFACE COURSE (1/2")	94	TON
SP & 412	COLD MILLING ASPHALT PAVEMENT	622	SQ. YD.
SP, SS, & 414	ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC	12	TON
SP, SS, & 415	ACHM PATCHING OF EXISTING ROADWAY	25	TON
SP, SS, & 504	APPROACH SLABS	126.38	CU. YD.
SP, SS, & 504	APPROACH GUTTERS	16.80	CU. YD.
601	MOBILIZATION	1.00	LUMP SUM
SP & 602	FURNISHING FIELD OFFICE	1	EACH
SS & 603	MAINTENANCE OF TRAFFIC	1.00	LUMP SUM
SS & 604	SIGNS	233	SQ. FT.
SS & 604	BARRICADES	64	LIN. FT.
SS & 604	TRAFFIC DRUMS	108	EACH
SS & 604	FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER	230	LIN. FT.
604	CONSTRUCTION PAVEMENT MARKINGS	8972	LIN. FT.
604	REMOVABLE CONSTRUCTION PAVEMENT MARKINGS	1028	LIN. FT.
SP	CULVERT CLEAN OUT	5	EACH
SP, SS, & 606	18" SIDE DRAIN	312	LIN. FT.
SP, SS, & 606	24" SIDE DRAIN	30	LIN. FT.
SP, SS, & 606	36" SIDE DRAIN	122	LIN. FT.
SS & 606	21" X 15" SIDE DRAIN	56	LIN. FT.
SS & 606	SELECTED PIPE BEDDING	40	CU. YD.
SS & 611	4" PIPE UNDERDRAINS	1000	LIN. FT.
SS & 611	UNDERDRAIN OUTLET PROTECTORS	8	EACH
SS & 617	GUARDRAIL (TYPE A)	450	LIN. FT.
SS & 617	GUARDRAIL TERMINAL (TYPE 2)	4	EACH
SS & 617	THRIE BEAM GUARDRAIL TERMINAL	4	EACH
620	LIME	7	TON
620	SEEDING	3.56	ACRE
SS & 620	MULCH COVER	7.12	ACRE
620	WATER	435.7	M. GAL.
621	TEMPORARY SEEDING	3.56	ACRE
621	SILT FENCE	5110	LIN. FT.
621	SAND BAG DITCH CHECKS	242	BAG
621	SEDIMENT BASIN	100	CU. YD.
621	OBLITERATION OF SEDIMENT BASIN	100	CU. YD.
621	SEDIMENT REMOVAL AND DISPOSAL	315	CU. YD.
621	ROCK DITCH CHECKS	45	CU. YD.
623	SECOND SEEDING APPLICATION	3.56	ACRE
635	ROADWAY CONSTRUCTION CONTROL	1.00	LUMP SUM
718	REFLECTORIZED PAINT PAVEMENT MARKING WHITE (6")	5000	LIN. FT.
718	REFLECTORIZED PAINT PAVEMENT MARKING YELLOW (6")	5000	LIN. FT.
721	RAISED PAVEMENT MARKERS (TYPE II)	32	EACH
SS & 731	TEMPORARY IMPACT ATTENUATION BARRIER	1	EACH
SS & 731	TEMPORARY IMPACT ATTENUATION BARRIER (REPAIR)	1	EACH
SS & 804	REINFORCING STEEL-ROADWAY (GRADE 60)	16108	POUND
<b>STRUCTURES OVER 20' SPAN</b>			
205	REMOVAL OF EXISTING BRIDGE STRUCTURE (SITE NO. 1)	1.00	LUMP SUM
636	BRIDGE CONSTRUCTION CONTROL	1.00	LUMP SUM
801	UNCLASSIFIED EXCAVATION FOR STRUCTURES-BRIDGE	63	CU. YD.
SP, SS, & 802	CLASS S CONCRETE-BRIDGE	88.40	CU. YD.
SP, SS, & 802	CLASS S(AE) CONCRETE-BRIDGE	292.60	CU. YD.
SP & 803	CLASS 2 PROTECTIVE SURFACE TREATMENT	798.1	SQ. YD.
SS & 804	REINFORCING STEEL-BRIDGE (GRADE 60)	29520	POUND
SS & 804	EPOXY COATED REINFORCING STEEL (GRADE 60)	77630	POUND
SP, SS, & 805	STEEL SHELL PILING (20" DIAMETER)	735	LIN. FT.
SP, SS, & 805	STEEL SHELL PILING (24" DIAMETER)	640	LIN. FT.
SS & 805	PILE ENCASEMENT	90	LIN. FT.
SS & 805	PREBORING	140	LIN. FT.
SP, SS, & 807	STRUCTURAL STEEL IN BEAM SPANS (A709, GR. 50W)	151970	POUND
SS & 807	PAINTING STRUCTURAL STEEL	33.4	TON
812	BRIDGE NAME PLATE (TYPE D)	1	EACH
SS & 816	FILTER BLANKET	575	SQ. YD.
SS & 816	DUMPED RIPRAP	387	CU. YD.

### REVISIONS

DATE	REVISION	SHEET NUMBER
7/19/2024	REMOVED SP FROM 21" X 15" SIDE DRAIN ITEM NUMBER, REVISED ORDER OF UTILITY ADJUSTMENT SPECIAL PROVISION APPENDIX	18

SUMMARY OF QUANTITIES AND REVISIONS