





DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
					6	8
				JOB NO.	100963	3

QUANTITIES, SUM. OF QUANTITIES, & REV.

**CLEANING AND PAINTING EXISTING STRUCTURAL STEEL (TYPE II)**

DESCRIPTION	QUANTITY	UNIT
BRIDGE NO. 06279	274	TON

THIS BRIDGE WAS DAMAGED BY A TRUCK ACCIDENT AND SUBSEQUENT FIRE THAT LEFT SOOT AND RESIDUE ON THE BRIDGE. STRUCTURAL REPAIRS HAVE BEEN COMPLETED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OF THE STEEL PRIOR TO PAINTING AND DISPOSAL OF ALL WASTE IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS.

**\*DISPOSAL OF HAZARDOUS WASTE**

DESCRIPTION	QUANTITY	UNIT
BRIDGE NO. 06279 (SITE NO. 1)	1.00	LUMP SUM

\* POTENTIAL HAZARDOUS WASTE IN THE FORM OF LEAD PAINT DEBRIS WILL BE REMOVED FROM THIS STRUCTURE AND SENT TO AN APPROPRIATE TREATMENT FACILITY AS PER CODE OF FEDERAL REGULATIONS 40 CFR PART 260.

**MOBILIZATION**

DESCRIPTION	QUANTITY	UNIT
ENTIRE PROJECT	1.00	LUMP SUM
TOTAL	1.00	LUMP SUM

**\*\*MAINTENANCE OF TRAFFIC**

DESCRIPTION	QUANTITY	UNIT
ENTIRE PROJECT	1.00	LUMP SUM
TOTAL	1.00	LUMP SUM

\*\* ALL TRAFFIC CONTROL DEVICES AND/OR PAVEMENT MARKINGS WILL BE PLACED IF AND WHERE APPROVED BY THE ENGINEER. ALL ITEMS NECESSARY FOR TRAFFIC CONTROL IS SUBSIDIARY TO THE ITEM OF "MAINTENANCE OF TRAFFIC".

**SUMMARY OF QUANTITIES**

LOCATION			BRIDGE DATA		ITEM NO.	SP & 820	601	SP & 603	820	
BRIDGE NUMBER	RT/SEC LOG MILE	COUNTY	ROADWAY WIDTH (FT)	ROADWAY LENGTH (FT)	BRIDGE NAME	PAY ITEM	CLEANING AND PAINTING EXISTING STRUCTURAL STEEL (TYPE II)	MOBILIZATION	MAINTENANCE OF TRAFFIC	DISPOSAL OF HAZARDOUS WASTE (SITE NO. )
						UNIT				
06279	1B/17B/2.94	CRAIGHEAD	76	252	HWY 1B OVER I-555	TON	274	LUMP SUM	LUMP SUM	LUMP SUM
TOTAL JOB NO. 100963							274	1.00	1.00	1.00 (SITE NO. 1)

**REVISIONS**

DATE	REVISION	SHEET NO.



QUANTITIES, SUMMARY OF QUANTITIES, AND REVISIONS